



Your Independent Bushing Supplier

Ihr unabhängiger Durchführungslieferant

DURESCA®-Wall Bushings

Capacitance fine graded with

RIP (Resin Impregnated Paper) dry type insulation material.

Manual for Installation

Maintenance and Storage







DE 17.5 kV - 2500 A

Product range

Unsere Produktpalette

Duresca®

Busbar systems Schienensystem



DEMI 145 kV - 800 A

Duresca®

Wall bushings Wanddurchführungen



Tiresca®

Busbar systems Schienensystem



DTOI 123 kV - 1250 A

Travesca®

Transformer bushings Transformator-Durchführungen



Gaslink®


SF₆ insulated busbar systems SF₆ isoliertes Schienensystem

Content

1.	Des	cription	4
	1.1.	Design	4
	1.2.	Application	5
	1.3.	Description	5
	1.4.	Version with high-quality coating DM/ DMI/DM2I	5
	1.5.	Version with polyamide tube DEM/DEM/DEMI/DEM2I	5
	1.6.	Version with silicone insulator DMI/DM2I/DEMI/DEM2I	5
	1.7.	Standard operating conditions:	6
2.	Trai	nsport, storage and handling	7
	2.1.	Packaging	7
	2.2.	Removal from the case.	8
	2.3.	Mounting and grounding	9
	2.4.	Recommended checks before connecting the voltage	10
	2.5.	Maintenance during service work	10
3.	Spe	cial attention for wall bushing with current transformer	13
	3.1 Se	condary connection	13
4.	Stor	age	14

1. Description

1.1. Design



	Protection of the RIP body				
	Application incoming		Application outgoing		
DM	Indoor	High quality coating	Indoor	High quality coating	
DMI	Indoor	High quality coating	Outdoor	Silicone insulator*	
DM2I	Outdoor	Silicone insulator*	Outdoor	Silicone insulator*	
DEM	Indoor	Polyamide tube	Indoor	Polyamide tube	
DEMI	Indoor	Polyamide tube	Outdoor	Polyamide tube and silicone insulator*	
DEM2I	Outdoor	Polyamide tube and silicone insulator*	Outdoor	Polyamide tube and silicone insulator*	

^{*}Porcelain is also available on request.

1.2. Application

DURESCA® wall bushings are designed to conduct the electrical energy through a wall or a roof.

The electrical current is conducted by a round conductor in copper or aluminium. It is characterised by a compact design and a partial discharge-free operation.

DURESCA® wall bushings can be described as being maintenance-free.

1.3. Description

DURESCA® wall bushings have a dry insulation RIP (Resin Impregnated Paper).

The insulation lies directly on the conductor and consists of wrapped paper, which is impregnated with special epoxy resin under vacuum. Conductive grading layers are embedded during the wrapping of the paper insulation for the optimal distribution of the electrical field. This structure ensures the longest possible operational reliability and the highest possible human safety.

1.4. Version with high-quality coating DM/ DMI/DM2I

To protect the RIP body of the bushing on indoor side, a high quality coating is applied on a thickness $30 - 40 \mu m$.

Resistant to water, dilute acids and chemicals. Excellent resistance against abrasion.

1.5. Version with polyamide tube <u>DEM/DEM/DEMI/DEM2</u>I

The polyamide tube provides:

- the best possible barrier against humidity and moisture ingress
- an excellent mechanical protection
- Additional creepage distance of about 16mm/kV in indoor application

1.6. Version with silicone insulator DMI/DM2I/DEMI/DEM2I

The silicone rubber insulator with alternating sheds has an uniform creepage distance of min. 31 mm/kV SCD or 53.7mm/kV USCD. This corresponds to a class 4 according to IEC 60815-1986 very high pollution level.

1.7. Standard operating conditions:

GENERAL

Standard IEC 60137-2008 Application Wall or roof

DESIGN

Type Fine Graded Condenser Type Insulation RIP Resin Impregnated Paper

Material Flange Made of corrosion free aluminium alloy

OPERATING CONDITIONS

 $\begin{array}{ll} \mbox{Altitude} & < 1000 \ \mbox{m} \\ \mbox{Ambient temperature} & -40 \ \mbox{up to } +40 \ \mbox{C} \\ \mbox{Mounting} & 0 \ \mbox{to } 90 \ \mbox{°} \end{array}$

Insulator outdoor Silicone or porcelain

Pollution class level Min 31mm/kV according to the IEC 60815-1986

For deviation, consult the specific datasheet from the corresponding bushing.

2. Transport, storage and handling



Warning

The function of the wall bushing is only guaranteed with the planned arrangement of components to each other. Severe malfunctions could otherwise occur. The installation instructions on the following pages must therefore always be followed absolutely. Local installation regulations are intended to ensure the safety of electrical installations. They are not taken into account in this operation manual, but must be observed in all cases.

2.1. Packaging

A special attention is taken for the packaging.

The bushings are packed in wooden crates for transportation.

All of our boxes are made of wood according to the ISPM 15 Standard. (ISPM: International Standards for Phytosanitary Measures)







Fig.3

All packaging has to be examined against damage during transport.

A copy from the Routine test is attached in the box.







DEM version



Fig.6

DEMI with current transformer

2.2. Removal from the case.

Small bushings can be taken by hand, larger require rope and lifting gear.

The bushings are secured as much as possible against transport damage.

The protective plastic bag must only be removed shortly before the assembly and installation.



Use of cutting tools is not recommended as it could damage the silicone sheds.

Please check the bushings for any transport damage immediately after the receipt of the goods.

In case of visual damage, proceed as following:

- 1. Inform the insurance from the carrier.
- 2. Declare the carrier as responsible on the Acknowledgement of receipt
- 3. Declare the carrier as responsible by registered letter. (In order to avoid prescribe the right of appeal against the carrier).

In case of transport under Moser-Glaser AG responsibility, the additional following points need to be followed:

4. MGC needs to be informed as quick as possible:

Tel. ++41 (0) 61 467 61 11 Fax. ++41 (0) 61 467 61 10 info@mgc.ch

5. A copy of the registered letter has to be sent to MGC

MGC Moser-Glaser AG Lerchenweg 21 CH-4303 Kaiseraugst (Switzerland)


If no damage has been observed, you can continue with the removal of the bushing.

2.3. Mounting and grounding

Bushings are fixed in the wall by 4 screws through the wall.

Sufficient clearances between live parts, wall, floor or grounded parts must be respected.

Lifting out by hand or using a crane



2.4. Recommended checks before connecting the voltage

MGC Moser-Glaser AG recommends that the following checks be carried out after the installation of the bushing in order to ensure safe operation:

- ✓ Check that the bushing is grounded
- ✓ When the bushing is equipped with a test tap, measure the tan δ and capacity cf. page 11.

2.5. Maintenance during service work

The MGC Moser-Glaser AG bushing is maintenance-free.

We recommend a control every 5 to 10 years

The following check may be made during inspection:



Danger to life! Work on the bushing must never be carried out when energized.

Silicone insulator cleaning.

Hydrophobic properties of silicone rubber cause far lower leakage currents, which results in excellent behaviour in polluted environments. Thus, there is no need for washing or greasing, even in humid or polluted areas, which saves on maintenance and cleaning costs. Silicone disables the formation of conductive paths, which lead to flashovers, line outages, and erosion of the insulator.

In case of exceptional severe site conditions, the insulators can be cleaned manually with soapy water and soft cloth.

No oils or detergents should be used.

Silicone rubber retains its hydrophobicity after washing.



Note


Clause 4.10 from IEC 60137-2008 mention that test tap is mandatory for transformer bushings with Um≥72.5kV

MGC can provide on request for its wall bushings a test tap


Capacitance and tangent delta measurement.

*Only valid if the bushing is equipped with a Test tap

Principle of functioning:



The test tap is designed for testing under an industrial frequency of 2kV.



Measurement of the Capacitance and Tangent delta are made during the routine test and reported in the test report provided with the bushing.

Capacitance measured during routine test is engraved at the nameplate for bushings with Um > 100kV. These values represent the references for the following measurement made on site.

• We recommend making a second reference measurement before the electrisation on-site.

Capacitance C1	Under the same test conditions should not increase by more than 5-7%
	For new bushings, is in the range of 0.4 to 0.7% and should not increase by more than 0.10% at $1.05 Um/\surd 3$ or Um
angent delta	Tangent Delta is temperature linked, when possible, measurement needs to be done at an ambient temperature of 20°C for a direct comparison with factory measurement, otherwise contact MGC for other conditions.

These values can be influenced by the methods, equipment, position of the bushing (vertical or horizontal) and conditions on-site, humidity, pollution, weather...

In standard the Test tap is not self-grounded. The cap has to be screwed tightly after measurement (30Nm).



Fig.11

In option MGC can provide Self-earthed test tap.



Fig.12





Warning



Note

The measurement connection may only be used when the voltage supply is switched off. After making the measurements, the measurement connection cover must always be screwed in again.

3. Special attention for wall bushing with current transformer



3.1 Secondary connection

Before making the secondary connections, it is essential to ensure that the installation is switched off and grounded. Be careful also of electromagnetic fields coming from nearby power plants.

The secondary connection must be carried out according to the scheme presented in the cable box.

To ensure the accuracy of the measuring transformer, the secondary line section must be sufficiently dimensioned.





Warning

- Do not put into service with a secondary circuit open! High voltage will be produced on secondary terminals!
- Each secondary circuit must be grounded at one point.
- Unused CT windings must be short circuited over the highest tap.





Fig.14

Example of cable box and nameplate for CT with two cores

4.Storage

For any duration, chose an indoor location which will be protected again rain and humidity.

Bushings should remain in original transport box, unpacked.

Contact MGC when long term storage is required.

If you have any doubt about after storage not appropriated, proceed to a capacitance and tan delta measurement if the bushing is equipped with a test tap.

If measured data deviate too much compared to the routine test provided, please contact MGC.

NOTE:	

This operation manual is also available in German, French and Russian.

Please contact your local representative.

 Created:
 27.11.2012
 28.11.2012
 28.11.2012
 WD-D001-E

 LVL
 SMU



MGC Moser-Glaser AG Lerchenweg 21 CH-4303 Kaiseraugst Switzerland / Schweiz

Phone +41 61 467 61 11 Fax +41 61 467 61 10 Internet www.mgc.ch E-Mail info@mgc.ch

Represented by / Vertreten durch:

